

## **EXCEL** Series

## Low Profile Dump Trailer 7,000lb-10,000Lb GVW

Ordered By:					Dealer:					
PO#:	:				Date:					
Standard Fo	eatures:									
					Fenders:	14 ga Tread Plate				
	5/16" Grade 70 w/Grab Hooks				Pockets:	Preformed - 3/16", no rub rail				
	102" Overall, 83" Inside Box				Endgate:	2 Way				
					Wiring:	Arctic Wiring, Soldered & Enclosed in Condui				
	Electric Brakes, Grease Hubs, 5 Stud				Lights:	LED, Rubber Mounted				
	Double Eye Leaf Springs w/Equalizers				Decking:	10ga Floor				
-	8 Ply Tires w/Modular Rims				Toolbox:	A-Frame (Hydraulic Housing)				
	5" Channel				Finish:	Sand Blast, Prime, Paint w/PPG Urethane				
amps:	Not Included	d			Rear Stabilizers:	Not Included				
harger:	110 Inverter	r Charger			Tarp Kit:	Not Included				
Rings:	Weld on 3" D Ring x 4				Wireless Remote:	Not Included				
MODEL:										
Quantity:					one type of trailer per order form.					
Select Model	Side Height	Floor/Sides	Axle Size	Tire & Rim	Tare Weight	Carrying Capacity	Hoist	Landing	Gate	
ELP76-10		10G/12G	2:3500lb	205/75R15	2450lb	3 Yards/ 5,328lbs	2 Ton	1:8000lb	2 Way	
ELP76-12	18"	10G/12G	2:3500lb	205/75R15	2610lb	4 Yards/ 5,168lbs	2 Ton	1:8000lb	2 Way	
OPTIONS:										
250ES =	2-5000Lb Elec/Spr				R3W =	Weld on 3" D ring				
SP1 =	Spare-205/7	75R15-8ply (3	500Lb)		MT6 =	Tarp-6' Wide Mesh				
SP2 =	Spare-ST22	25/75R15-8ply	(5000Lb)		APR =	Adjustable Pintle Ring				
AW1 =	Alum wheel	upgrade-15"			ABM =	2 5/16" Adjustable Coupler				
	Double A R					Rear Stabilizers (Tube)				
PG =	Charcoal G	rey			R6T =	6'x12" tube ramps				
	Solar Panel				DH =	Document Holder				
WRK =	Wireless Remote for Pwrpack									
otes:										
							Signature:			