



Pro Series

Low Profile Dump Trailer 14,000lb GVW

Ordered By: _____

Dealer: _____

PO#: _____

Date: _____

Standard Features:

| | | | |
|-------------------------|--------------------------------------|--------------------------|---|
| Coupler: | 2-5/16" Adjustable Channel Mount | Fenders: | 14 ga Tread Plate |
| Safety Chains: | 5/16" Grade 70 w/Grab Hooks | Pockets: | Preformed - 3/16" w/Full Length 1/4" Rubrail |
| Width: | 102" Overall, 83" Inside Box | Endgate: | 3 Way Spreader Gate |
| Deck Height: | 27" | Wiring: | Arctic Wiring, Soldered & Enclosed in Conduit |
| Axles: | Electric Brakes, Grease Hubs, 8 Stud | Lights: | LED, Rubber Mounted |
| Suspension: | Leaf Springs w/Equalizers | Decking: | 3/16" Floor |
| Tires & Rims | 10 Ply Tires w/Modular Rims | Toolbox: | A-Frame (Hydraulic Housing) |
| Main Frame: | 8" Wide Flange Beam | Finish: | Sand Blast, Prime, Paint w/PPG Urethane |
| Wireless Remote: | Not Included | Ramps: | Not Included |
| Charger: | 110 Inverter Included | Rear Stabilizers: | RS1 Included |
| D Rings: | Weld on 4" D Ring x 4 | Tarp Kit: | Not Included |

MODEL:

Quantity: _____

****NOTE** Only one type of trailer per order form.**

| Select Model | Side Height | Floor /Sides | Axle Size | Tire & Rim | Tare Weight | Carrying Capacity Cubic | Hoist | Landing Gear | Gate |
|--------------|-------------|--------------|-----------|------------|-------------|-------------------------|-------|--------------|-------|
| LP147-12 | 21" | 3/16 /12G | 2:7000lb | 235/80R16 | 3850 | 6 Yards/ 11,706lbs | 7 Ton | 1:12,000lb | 3 Way |
| LP147-14 | 21" | 3/16 /12G | 2:7000lb | 235/80R16 | 4290 | 7 Yards/ 11,266lbs | 7 Ton | 1:12,000lb | 3 Way |
| LP147-16 | 21" | 3/16 /12G | 2:7000lb | 235/80R16 | 4730 | 8 Yards/ 10,826lbs | 7 Ton | 1:12,000lb | 3 Way |

OPTIONS:

| | |
|---|--|
| 270ET = 2-7000Lb Elec/Tor | R7 = 7' Slide In Ramps |
| SWB = Wet Bolt Equalizer (7k axles) | R7HD = 7' HD Slide In Ramps |
| SP3 = Spare-ST235/80R16-10ply-single | R4W = Weld on 4" D ring |
| SP5 = Spare-ST235/85R16-14ply-single | MT7 = Tarp-7' Wide Mesh |
| USP5 = ST235/85R16-14ply Upgrade | RS3 = Rear Stabilizer Jacks (7k Jack) |
| AW2 = Alum wheel upgrade-16" | H3 = Upgrade Hoist -7 to 10 Ton |
| PDA = Double A Red | DH = Document Holder |
| PG = Charcoal Grey | P5 = Quick Connect Power Cable |
| GN2 = GN w 2-12k jacks | P6 = Solar Panel |
| GKP = GN King Pin | CW2 = Quick Charge - 12v (20amp) |
| NR4 = Raise Neck 4" | WRK = Wireless remote for Pwrpack |
| UD = Upper Deck | CP7 = Commercial Plug |

Notes:

| | |
|--|-------------------|
| | Signature: |
|--|-------------------|